



No.	Material	WT.
700'	8" Pipe (C.I.)	31,500
500'	1 1/2" Galvanized Pipe	
1	1 1/2" Valve	
3	6" Valves	495
1	Pressure Reducing Valve	300
1	8x6" Tee	270
1	6"-22 1/2° Bend	105
1	Fire Hydrant (Special)	500
1	8" Plug	24
1	6"x90° Bend	130
7	Valve Boxes	525
2	8" Valves	550
1	1 1/2" Corp. Cock	
1	6" Plug	14
800'	6" Pipe (C.I.)	23,000
1	8x6" Reducer	150
1	6" Tee	200

W.O. No. C-153.  
 Issued for construction - 1948  
 Revised 28 Aug 48 - Rwy crossing was further east.

<b>PUBLIC SERVICE COMMISSION</b>	
HALIFAX WATERWORKS SYSTEM	
8" & 6" WATER MAIN EXTENSION TO AFRICVILLE.	
TT-52-32950	
DRAWN BY: H.R.C.	SCALE: 1" = 100'
CHECKED BY: Δ	DATE: Feb. 20, 1948
APPROVED:	No. D-149