HALIFAX

Dutch Village Road Complete Streets











June 9, 2020





Project Rationale

- The *Integrated Mobility Plan* was unanimously approved by Regional Council in December 2017.
- Action A69 of the IMP identifies Dutch Village Road as a Priority Sidewalk Connection.
- Active Transportation Priorities Plan identifies
 Dutch Village Road as a Candidate Bicycle Route.
- Increased residential intensification enabled by recent MPS and LUB amendments.







Project Objectives


- Confirm vision of the corridor's function as a street and a place
- Understand how the corridor currently functions
- Identify potential configuration options for the corridor that:
 - > Fill in the active transportation and transit gaps along the corridor
 - > Improve quality of transportation infrastructure for all users
- Understand and justify potential trade-offs





Dutch Village Road

- ~700m section connecting Joseph Howe
 Drive & Alma Crescent
- Functional Plan initially excluded the Bayers Road / Joseph Howe Drive & Alma Crescent / Supreme Court intersections





HALIFAX

Existing Conditions: Corridor Cross-Section









Parking encroaches on right of way Access is Uncontrolled

56 collisions over 3 years







ofo



Recommended: Corridor Cross-Section



Raised protected bicycle lanes on both sides of the street

Accessible bus stops

Improved access management by eliminating nose-in parking


Four small parcels required for acquisition


Streetscaping allowance





Existing Conditions: Joseph Howe Drive / Bayers Road










Recommended: Joseph Howe Drive / Bayers Road

 Extend bicycle lanes to Chain of Lakes Trail (COLT)


Corners:


- A) Removal of right turn channel
- B) Removal of receiving lane
- C) Potential for future bump-out
- D) Potential for decrease in radius





Existing Conditions: DVR / Supreme Court / Alma Crescent










Recommended: DVR / Supreme Court / Alma Crescent

- Extend bicycle lanes to intersection
- Removal of right turn channel
- Painted bike lane that transitions to raised bike lane after driveways







Next Steps / Implementation

- Detailed design will be advanced (2020/2021)
- Property acquisition process is underway
- \$2.25 million identified for construction (2021/2022)



Acknowledgments

Consulting Team

Funding Partner





