## **EROSION & SEDIMENT CONTROL**

- ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE CONSTRUCTED AND MAINTAINED TO PROTECT ALL NATURAL WATERCOURSE FROM DAMAGE DUE TO SILT LADEN RUN-OFF FROM CONSTRUCTION.
- RECOMMENDED CONSTRUCTION AND MAINTENANCE PROCEDURES MAY BE OBTAINED FROM THE LATEST REVISION OF "EROSION AND SEDIMENTATION CONTROL HANDBOOK FOR CONSTRUCTION SITE". PREPARED BY THE NOVA SCOTIA DEPARTMENT OF THE ENVIRONMENT.
- PERIODICALLY INSPECT AND CORRECT EROSION AND SEDIMENTATION CONTROL MEASURES TO ENSURE CONTINUED EFFECTIVENESS.
- STABILIZE ALL DISTURBED AREAS TO PREVENT **EROSION IMMEDIATELY AFTER COMPLETION OF**
- PROTECT ALL POINTS OF CONSTRUCTION SITE ENTRANCE AND EXIT TO PREVENT TRACKING OF MUD ONTO PUBLIC STREETS.
- PRIOR TO COMMENCEMENT OF CONSTRUCTION INSTALL SILT CONTROL MEASURES SUCH AS SILT FENCE OR FILTER SPREADER OF GRAVEL FILTER.
- CONSTRUCT STORM SEWER TO DIVERT FLOW FROM OFF SITE DRAINAGE AWAY FROM THE WORK AREA. PUMP THE FLOW, IF REQUIRED AROUND THE WORK SITE.
- ANY SILT LADEN WATER PUMPED FROM THE TRENCH IS TO PASS THROUGH A FILTERING SYSTEM.

## CONCEPTUAL STORMWATER MANAGEMENT


THE PURPOSE OF THIS CONCEPTUAL STORM WATER MANAGEMENT PLAN IS TO ADDRESS THE POTENTIAL EFFECTS UPON WATER QUALITY AND QUANTITY FROM THE PROPOSED DEVELOPMENT.

THE GOAL OF THIS SWMP FOR STORMWATER QUANTITY CONTROL IS TO MATCH CLOSELY THE PRE-DEVELOPMENT HYDROLOGIC CONDITIONS TO THE POST-DEVELOPMENT CONDITIONS (NO NET INCREASE IN PEAK FLOW RESULTING FROM THE PROPOSED DEVELOPMENT).

#### STORMWATER QUANTITY AND QUALITY CONTROLS FOR THIS DEVELOPMENT MAY INCLUDE:

ATTENUATED AND DRAINED AT A CONTROLLED RATE.


- CONTROL POST-DEVELOPMENT PEAK FLOWS FROM THE 5 AND 100 YEAR 24 HOUR STORM EVENTS.
- MULTI-UNIT RESIDENTIAL BUILDING ROOFS AND PODIUMS SO THAT STORM WATER IS DETAINED AND DRAINED AT A CONTROLLED RATE.
- DIRECT RUNOFF FROM DRIVEWAYS AND PARKING AREAS TO THE BIORETENTION AREA (RAIN GARDEN) SO THAT STORM WATER IS RETAINED,
- SURFACE DETENTION COMBINED WITH ROOF & PODIUM STORAGE AND THE EXISTING DEPRESSIONS AND PONDS CAN BE INCORPORATED TO CONTROL THE POST DEVELOPMENT STORM WATER FLOWS TO PRE-DEVELOPMENT CONDITIONS.
- BIORETENTION AREA VEGETATION AND SOIL MEDIUM SHALL BE SELECTED TO ENSURE STORM WATER QUALITY ENHANCEMENT.
- RETAIN ON-SITE STORM WATER RUNOFF GENERATED FROM THE FIRST 10mm DEPTH OF A RAINFALL EVENT. (VOLUME OF INTERNAL WATER STORAGE WITHIN THE BIORETENTION SYSTEMS)





\_2"x4"x4' POST GEOTEXTILE FENCE NVIROFENCE) GRADE - 2± SILTATION FENCE TEMPORARY GRAVEL CONSTRUCTION ENTRANCE N.T.S.

6'-0" (TYP.)

2"x2"x4' POST-










STORM WATER IS DETAINED AND DRAINED AT A CONTROLLED

RATE FROM THE ROOF.



DETENTION





MINIMUM 400 DEEP CLEAR

STONE WRAPPED WITH

GEOTEXTILE —

400± DEEP ENGINEERED

SOIL, MAINLY SAND.



# CONCEPTUAL **STORMWATER MANAGEMENT**

# MONTAGUE DEVELOPMENT

MONTAGUE ROAD			WESTPHAL, N.S.
DRAWN	DATE	PLAN NO.	
M.D.M.	NOVEMBER 22, 2022		22-187-0 <b>2</b>
ENGINEER SOORI	SCALE NTS U/N	SHEET	2

CONSTRUCT A SWALE OVER AND ADJACENT TO THE PROPOSED STORM

PROPERTY BOUNDARIES.

AND OVERLAND FLOW

STORM WATER RUNOFF FROM THE PROPOSED DEVELOPMENT DRAINS TO THE EXISTING POND VIA THE PROPOSED STORM PIPE

DRAINAGE AREA TO 'A' - 26 Ha ±

DRAINAGE AREA TO 'B' - 2.5 Ha ±

PIPE TO CONVEY MAJOR OVERLAND FLOW CONTAINED WITHIN THE

1:2000