



LEVEL SPREADER N.T.S.



GRAVEL FILTER



OFF SITE CATCH BASIN
N.T.S.

## RAINFALL INTENSITY - DURATION - FREQUENCY VALUES

I = AT <sup>B</sup>
I = RAINFALL RATE (mm/hr)
T = TIME (hrs)

	5 YR.	10 YR.	100 YR.
COEFF. A	25.2	29.0	40.8
EXPONENT B	-0.557	-0.557	-0.555

IDF VALUES PUBLISHED BY ENVIRONMENT CANADA FOR SHEARWATER AIRPORT WEATHER STATION BASE DATA FOR THE PERIOD 1955 - 1997.


#### **EROSION & SEDIMENT CONTROL**

- ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE CONSTRUCTED AND MAINTAINED TO PROTECT ALL NATURAL WATERCOURSE FROM DAMAGE DUE TO SILT LADEN RUN-OFF FROM CONSTRUCTION.
- RECOMMENDED CONSTRUCTION AND MAINTENANCE PROCEDURES MAY BE OBTAINED FROM THE LATEST REVISION OF "EROSION AND SEDIMENTATION CONTROL HANDBOOK FOR CONSTRUCTION SITE", PREPARED BY THE NOVA SCOTIA DEPARTMENT OF THE ENVIRONMENT.
- PERIODICALLY INSPECT AND CORRECT EROSION AND SEDIMENTATION CONTROL MEASURES TO ENSURE CONTINUED EFFECTIVENESS.
- STABILIZE ALL DISTURBED AREAS TO PREVENT EROSION IMMEDIATELY AFTER COMPLETION OF
- PROTECT ALL POINTS OF CONSTRUCTION SITE ENTRANCE AND EXIT TO PREVENT TRACKING OF MUD ONTO PUBLIC STREETS.
- PRIOR TO COMMENCEMENT OF CONSTRUCTION INSTALL SILT CONTROL MEASURES SUCH AS SILT FENCE OR FILTER SPREADER OF GRAVEL FILTER.
- CONSTRUCT STORM SEWER TO DIVERT FLOW FROM OFF SITE DRAINAGE AWAY FROM THE WORK AREA. PUMP THE
- FLOW, IF REQUIRED AROUND THE WORK SITE.

  ANY SILT LADEN WATER PUMPED FROM THE TRENCH IS TO PASS THROUGH A FILTERING SYSTEM.

### PRE-DEVELOPMENT CONDITION

102 ●



## OTTHYMO MODEL SCHEMATIC

# OTTHYMO MODEL SUMMARY OF UNIT HYDROGRAPH PARAMETERS

DRAINA	AGE AREA	NA		SHYD	
#	AREA (Ha)	CN	IA (mm)	N	TP (HRS)
101	3.6	77	5.0	3	0.10
102	8.2	75	5.0	3	0.15

### PRE-DEVELOPMENT PEAK FLOW ESTIMATES

REFERENCE	PEAK FLOW (cms)		
POINT	5 YR.	10 YR.	100 YR.
TO BISSETT RUN	0.42	0.67	1.11

## POST-DEVELOPMENT STORMWATER

- ON-SITE DETENTION STOARGE (COMBINED VOLUME OF SURFACE PONDING AND UNDERGROUND PIPE STORAGE) SHALL BE DESIGNED TO CONTROL THE POST DEVELOPMENT STORM WATER FLOWS TO PRE-DEVELOPMENT CONDITIONS.
- 2. STORMWATER MANAGEMENT PLAN INDICATES THAT THE REQUIREMENTS OF ADMINISTRATIVE ORDER 2020-010-OP RESPECTING STORMWATER MANAGEMENT STANDARD FOR DEVELOPMENT ACTIVITIES HAD BEEN CONSIDERED IN ORDER TO MEET ITS REQUIREMENT.
- 3. PRIOR TO COMMENCE CONSTRUCTION, STORMWATER MANAGEMENT FACILITIES SHALL BE DESIGNED TO MEET THE REQUIREMENTS OF ADMINISTRATIVE ORDER 2020-010-OP, SPECIALLY TO THE RETENTION OF ON-SITE STORMWATER RUN-OFF GENERATED FROM THE FIRST 10mm DEPTH OF A RAIN FALL EVENT, AND REMOVAL OF 80% OF TOTAL SUSPENDED SOIL (TSS).

3	31 MAY 24		ISSUED FOR APROVAL	1 h
2	14 FEB. 24		ISSUED FOR APROVAL	W2
1	22 APR. 23		ISSUED FOR APROVAL	ish.
NO.	DATE	R	EVISION DESCRIPTION	APPR'D
APRIL 22, 2023  M. Sooriyakamaran  4921  Shoreham development inc		THOROTON B	LANDS OF GEM HEALTH CARE GROUP PID 00403014 PID 00402768	

### PRELIMINARY STORMWATER MANAGEMENT DETAILS

## 1226 COLE HARBOUR ROAD

COLE HARBOUR ROA	COLE HARBOUR N.S	
DRAWN	DATE	PLAN NO.
MDM	22 APRIL 2023	23-303-03
ENGINEER	SCALE	SHEET
SOORI		3

