Whites Lake Property

Prospect Road, Whites Lake, Halifax County, Nova Scotia

Level I Groundwater Resources Assessment



Revision #1

prepared for:

Mr. Tom Lavers

W.G. Shaw & Associates Ltd. Consulting Geoscientists February 27, 2025

W.G. Shaw & Associates Ltd.

Consulting Geoscientists

4546 Highway #7
Antigonish, Nova Scotia
Canada B2G 2L3
phone (902) 863 - 1903
E-mail: wgshaw@eastlink.ca

Mr. Tom Lavers Prospect Road White's Lake, Nova Scotia Canada February 27, 2025

Re: Whites Lake Property, HRM, Nova Scotia

Level I Groundwater Assessment

Dear Mr. Lavers,

Please find enclosed our revised technical report on a Level I Groundwater Assessment for the Whites Lake Property, HRM, Nova Scotia.

Sincerely,



William G. Shaw, *Pigeon*. President



Table of Contents

1.0	Intr	oduction	p.	04
	1.1 1.2	General Description of Project Scope of Work	р. р.	04 04
	1.2	scope of Work	Ρ,	0 1
2.0	Natı	ıral Landscape and Climate	p.	06
	2.1	Natural Landscape and Topography	p.	06
	2.2	Climate and Precipitation	p.	06
	2.3	Surface Water Features	p.	07
	2.4	Wetlands	p.	08
3.0	Anti	cipated Demand and Supply of Water	p.	10
4.0	Sun	nmary of Hydrogeology	p.	11
	4.1	Surficial Sediments	p.	11
	4.2	Bedrock	p.	11
	4.3	Regional Groundwater Flow	p.	12
5.0	Wat	er Supply Wells and Water Quantity	p.	13
	5.1	Water Supply Wells in the Area	p.	13
	5.2	Well Yields	p.	15
6.0	Wat	er Balance (Groundwater Recharge)	p.	17
7.0	Exp	ected Water Quality	p.	19
8.0	Eva	luation of Potential Effects	p.	20
	8.1	Potential Well Interference	-	21
	8.2	Potential Effects on Surface Water and the Environment	-	21
	8.3	Risk of On-Site Septic Systems on Water Wells	-	21
	8.4	NSECC Well Construction Regulations	-	21
	8.5		p.	$^{\circ}$
9.0	Sun	nmary	p.	22
Appe	ndix A	Survey Plan of Property	p.	23
Appe	ndix I	B Drillers Report for Well in Lot H	p.	24

1.0 Introduction

1.1 General Description of the Project

W.G. Shaw & Associates Ltd. (WGSL) was retained by Mr. Tom Lavers to conduct a Level I Groundwater Assessment for a proposed residential development (the Property), located at Whites Lake, Halifax County, Nova Scotia (Figures #1, #2 and #3).

The Property is a northeast-trending, roughly rectangular-shaped parcel of land that is approximately 500 metres long by 240 metres wide with a total area of 11.6 hectares (PID #0038 1715)(Figure #6 and Appendix A).

Future plans are to subdivide the Property into twelve (12) individual residential lots including one single-family dwelling with its own private water supply well (one well per lot).

1.2 Scope of Work and Methodology

In order to fulfill the requirements, we followed the Nova Scotia Environment's Guide to Groundwater Assessments for Subdivisions Serviced by Private Wells, Level I. These included the review, compilation and interpretation of the following sources of information and data:

- Geologic Reports and Maps: surficial sediments and bedrock geology
- Topographic Maps:
- Air Photos
- Water Wells Records: Nova Scotia Well Logs Database and Groundwater Atlas, well construction records, pump tests records and water quality records.
- Historical Pump Tests: wells and aquifers
- Nova Scotia Pump Test Database
- Watershed Maps: primary, secondary, tertiary
- Climate Data: annual precipitation patterns
- Nova Scotia Groundwater Toolkit



Figure #1 Location of Whites Lake Property on Regional Map



Figure #2 Location of White's Lake Property on Topographic Map

2.0 Natural Landscape and Climate

2.1 Natural Landscape and Topography

The Property is located within the Pennant Granite Barrens Natural Landscape of Nova Scotia. This landscape is characterized by low undulating terrain dominated by a mosaic of boreal and coastal coniferous forests with interspersed barrens.

The Property lies within a parcel of land that slopes gently toward the west from a maximum elevation of 80 metres on the east side to 60 metres on the west side (Figures #2 and #6).

2.2 Climate and Precipitation

Climate normals for the Property are derived from the Environment Canada (EC), climate monitoring station located at St. Margaret's Bay which is located approximately 22 kilometres to the northwest. The results indicate the area receives total annual precipitation of from 1,300 to 1,400 millimetres of normal which 85% occurs as rain. The average total annual precipitation for the 1981 to 2010 period was 1,380 millimetres (1.38 metres).




Figure #3 Climate Normals for the St. Margaret's Bay Climate Station from 1981 to 2010

2.3 Surface Water Features

The Property lies within the Sackville River Primary Watershed and within the Prospect River Secondary Watershed (Figures #5 and #6). There are no watercourses on the Property. Surface water runoff is by overland flow toward the west in the direction of the Prospect River which is located 600 metres west of the Property (Figures #4 and #5).




Figure #4 Primary Watersheds of Nova Scotia




Figure #5 Secondary Watersheds of Nova Scotia


2.4 Wetlands

In Nova Scotia, a wetland is a term that includes the land areas that are commonly referred to as a marsh, swamp, fen or bog that either periodically or permanently has a water table at, near or above the land's surface or that is saturated with water. These land areas sustain aquatic processes as indicated by the presence of poorly drained soils, hydrophytic vegetation and biological activities adapted to wet conditions.¹

A search of the Nova Scotia Ecological Land Classification mapping indicates there are no significant wetlands within the Property or within 1 kilometre of the Property.

3

¹ NS Environment Act as amended in 2006



Explanation

Residential Building (private well)

W.G. Shaw & Associates Ltd. Consulting Geoscientists



Antigonish, Nova Scotia Canada Phone: 902-863-1903

Whites Lake Property

Whites Lake, Nova Scotia

Figure #6

February, 2025

3.0 Anticipated Demand and Supply of Potable Water

3.1 Anticipated Demand

Considering proposed plans for the Property consist of the construction of up to 12 residential units with an average number of 3.0 people for each unit the following provides a summary of the anticipated water use per day.

Number of Residential Units	=	12	units
Number of People Per Unit	=	3.0	
Total Number of People Served	=	36	people
Water Use Per Person Per Day	=	240	<u>litres</u>
Total Maximum Water Use Per Day	=	8,640	litres/day

Therefore, at full build-out, the total maximum daily water use is expected to be in the range of 8,000 to 10,000 litres.

3.2 Anticipated Supply

Future plans are to subdivide the Property into twelve (12) individual residential lots each containing one single-family dwelling with its own private water supply well (one well per lot).

4.0 Summary of Hydrogeology

4.1 Surficial Sediments

The Property is covered by a layer of surficial sediments that consist of yellowish-grey coloured, gravely silt and clay (glacial till) which, according to local drilled well records are from 1 to 8 to metres thick.

4.2 Bedrock Hydrogeology

The Property is underlain by bedrock that consists of orangish-grey coloured granite where all of the porosity, permeability and storage of groundwater is within fractures in the bedrock (Illustration #1).




Illustration #1 Schematic Illustration of a Fractured Rock Aquifer System

Permeability of a fractured rock aquifer is dependent on the following factors:

- the number of fracture sets
- · the orientation of the fracture sets
- · the density of the fracture surfaces (spacing)
- the aperture of the fractures (distance between walls of fractures), and
- the degree of interconnection of the fracture sets.

Fractured rock aquifers generally have a much lower capacity to transmit water than sand & gravel aquifers or sandstone aquifers. This lower capacity results from both a smaller amount of open space (porosity) and heterogeneities of the fracture patterns that are always present in the aquifer as compared to the primary permeability found in sand & gravel and sandstone aquifers. As a result, many fractured rock aquifers are limited in the amount of water they can reliably produce in the long term and should be assessed in a cautious manner.

4.3 Regional Groundwater Flow

Based on topography and hydrogeology, regional groundwater flow direction is anticipated to be a subdued replica of the topographic surface which is toward the west.

Recharge to the granite, bedrock aquifer is from rainfall and snow melt infiltration both locally and areas hydraulically upgradient of the site on the east side of the Property.

5.0 Water Supply Wells and Water Quantity

5.1 Water Supply Wells in the Area

There are no water supply wells on the Property. In June of 2023, a water well was drilled adjacent to southwest corner of the Property as shown on Figure #6. The following is a summary of the well construction characteristics of this well.

5.1.1 Lot H Well

Total Depth 50.3 metres (165 feet) (152 mm; 6") =Casing 6.1 metres (20 feet) Screens none metres Bentonite Grout 6.1 metres Static Water Level 4.5 metres BTC Top of Bedrock 2.0 metres (6 feet) Producing Aquifer Bedrock (Granite) **Estimated Yield** 50 litres per minute (driller's estimate)

A review of topographic maps and air photos indicates there are approximately 80 residential properties within 500 metres of the Property boundaries, all of which have private house wells (Figure #6).

Research of the NSE Groundwater Atlas and NSE Drilled Well Database indicates NSE has records for 29 of these drilled wells (Table #1 and Figure #6). The NSE Drilled Well Database indicates these drilled wells have total depths of from 22.8 to 99.0 metres with driller's estimates of yields of from 2 to 114 with an average (mean) of 38 litres per minute².

² Driller's estimates of well yield are made by the drilling contractor after completion of well construction and are always greater than the sustainable yield of the well.

<u>Table #1</u><u>Whites Lake Property</u>Drilled Well Records in NSE Database

NSE Well	NSE Well	Community	Date	Total	Casing	Top of	Static Water	Well
Number	Address		Drilled	Depth	Depth	Bedrock	Level	Yield
			yr-mo-day	metres	metres	metres	metres	litres/minute
21,138	2588 Prospect Road	Whites Lake	2002-12-17	91.4	12.2	9.7	6.1	2
30,693	2660 Prospect Road	Whites Lake	2003-09-04	42.6	6.1	2.4	3.0	36
31,138	2540 Prospect Road	Whites Lake	2003-03-15	50.2	5.6	3.7		64
42,781	22 Rachael Avenue	Whites Lake	2004-06-11	42.6	7.0	4.3		68
51,152	32 Deepwood	Whites Lake	2005-03-15	99.0	6.1	3.7	6.1	2
51,173	31 Rachael Avenue	Whites Lake	2005-03-15	38.1	6.1	2.1	6.1	68
51,174	90 Rachael Avenue	Whites Lake	2005-03-15	38.1	8.5	6.1	6.1	68
51,336	Rachael Drive	Whites Lake	2005-05-16	42.6	10.1	5.5	3.0	65
61,182	Rachael Drive	Whites Lake	2006-03-15	44.2	12.2	9.1	6.1	45
80,297	2719 Prospect Road	Whites Lake	2008-07-23	42.6	6.1	1.2		27
100,616	26 Denford Road	Whites Lake	2010-06-23	42.6	7.3	3.4		20
150,001	32 A MacLane,		2015-01-12	56.3	9.1	5.5	3.0	14
180,109	2672 Prospect Road	Whites Lake	2018-04-16	48.7	12.2	1.8	3.0	36
180,945	2540 Prospect Road	Hatchet Lake	2018-12-04	80.7			1.5	23
200,530	2933 Prospect Road	Whites Lake	2020-10-29	44.2				68
831,163	Stoney Beach Road	Whites Lake	1983-08-26	42.6	6.1	0.3		5
841,088	Prospect Road	Whites Lake	1984-06-16	38.1	15.2	12.2	7.6	9
841,090	Prospect Bay	Whites Lake	1984-06-15	22.8	6.7		4.6	23
871,401	Stoney Beach Road	Whites Lake	1987-06-08	31.4	7.3	5.8	4.6	91
872,727	SITE 16 A	Whites Lake	1987-11-09	44.2	6.7			18
890,096		Whites Lake	1989-04-05	42.6	6.1	3.7		14
910,004		Whites Lake	1991-02-06	63.0	7.6	3.4	1.8	11
912,371	Sandstone Drive	Whites Lake	1991-07-02	32.0	6.7	1.8	6.1	36
930,478	Stoney Beach Road	Whites Lake	1993-05-31	30.5	6.1	2.7		18
940,765	Stoney Beach Road	Whites Lake	1994-04-28	32.0	8.5	0.9	2.4	68
951,022	Stoney Beach Road	Whites Lake	1995-06-13	31.4	7.3	5.5	3.7	45
960,372	2890 Prospect Road	Whites Lake	1996-05-30	54.8	7.0	5.8	4.9	10
970,138	2890 Prospect Road	Whites Lake	1997-05-12	75.2	6.1	4.6	4.6	114
970,776	2379 Prospect Road	Whites Lake	1997-09-30	42.6	6.1			18
Lot H Well	2740 Prospect Road	Whites Lake	2023-06-15	50.3	6.1	2.0	4.5	50
Minumum				22.8	5.6	0.3	1.5	2
Maximum				99.0	15.2	12.2		114
Average (Me	an)			47.9	7.8	4.3		38

Notes

¹⁾ Blank cells indicate there is no data in the NSE Database.

²⁾ Wells without civic addresses may not be within 500 metres of the Property.

5.2 Well Yields

A rough estimate of the anticipated yield of water wells to be constructed on the Property can be made using two methods: 1) using the Nova Scotia Department of Environment's Toolkit for Groundwater Assessments, and 2) comparing these results to driller's estimates of yields for the 33 well records within 500 metres of the Property that are in the NSE database.

Method #1

For Method #1, it is assumed the future test wells will be constructed to total depths of 70 metres, the pumps will be installed to depths of 60 metres and the deepest static water level will be 10 metres below grade. Using the transmissivity estimate for granite in the NSE Toolkit and applying the Farvolden formula for generating a calculated estimate of yields (Q_{20}), the results are as follows:

Method #1

Total Depth of Well(s)	=	70	metres (below ground surface)
Pump Depth	=	60	metres
Static Water Level	=	10	metres (below ground surface)
Saturated thickness	=	50	metres
Available drawdown (H _A)	=	37	metres (75% of saturated thickness)
Aquifer Transmissivity (T)	=	1.0	$m^3/day/m$ (from NSE Toolkit)
Safety Factor (Sf)	=	0.7	
Estimated Yield (rounded)	=	17.7	cubic metres per day
	=	17,700	litres per day
	=	12	litres per minute (rounded)
$Q_{20} = (0.683)(T)(H_A)(S_f)$)		Farvolden Method

Method #2

The second method of predicting the yields of wells to be constructed on the Property is to examine the well construction and yield data for existing wells located within 500 metres of the Property. Knowing that Driller's Estimates of well yield are significantly greater than the long term sustainable yield of most drilled wells, we have added a factor of 50% of Driller's Estimate significantly to generate the following:

Range of Well Depths	=	22.8 to 99.0	metres
Range of Driller's Estimates of Yield	=	2 to 114	litres/minute
Mean of Driller's Estimates	=	38	litres/minute
50% of Mean of Driller's Estimate	=	19	litres/minute

Therefore, the two methods of estimating yields of future wells to be constructed on the Property are in reasonable agreement with the results indicating anticipated well yields between 10 and 20 litres per minute.

6.0 Water Balance (Groundwater Recharge)

Considering proposed potable water supply to the Property will be provided by private wells with one well per lot, this water balance and groundwater recharge estimate utilizes the entire 11.6 hectare property as the recharge area (capture zone). In this method, we utilized the annual groundwater recharge estimate for the Sackville River Primary Watershed as published by the Nova Scotia Department of Environment of 197 mm, an estimated impervious surface estimate of 30% and NSE's recommended Ecological Maintenance Factor of 50%.

Ecological use refers to groundwater that helps maintain ecological habitats by discharging as baseflow to surface water bodies. Ecological use is assumed to be 50% of the groundwater recharge. The following are the inputs to generate the groundwater recharge estimate:

Table #2

Whites Lake Property

Long Term Water Balance & Groundwater Recharge

(for Properties with On-Site Septic Systems and Road Drainage Control)

Part A: Anticipated Daily Water Use

Number of Residential Units		12
People per Unit		3.0
Population Served		36
Water Use per Person per day	litres/day	240
Water Use Per Day	litres/day	8,640

Part B: Annual GW Recharge to Property

Total Recharge Area	hectares	11.6
	sq. metres	116,000
GW Recharge Rate (Sackville River Watershed)	metres/year	0.197
Impervious Surfaces	decimal	0.3
Pervious Surfaces	decimal	0.7
Ecologic Maintenance (NSE's Constant)	decimal	0.5
Engineering Design Credits (50% of annual water use)	cubic metres	1,577

Part C: Summary of Available Groundwater

Total Annual Recharge to Property	cubic metres	9,575
1907 190 300-01	litres	9,575,000
Daily Recharge to Property	litres/day	26,233

Therefore the long term groundwater recharge to the Property is estimated to be 26,000 litres per day (rounded) which is significantly more than the anticipated groundwater withdrawals of 8,000 to 10,000 litres per day.

7.0 Expected Water Quality

The NSE Water Quality Database does not contain any water quality data for groundwater samples within 500 metres of the Property. However, anecdotal evidence from well drilling contractors indicates the well water quality in the area is of general good quality.


The Property is located in a part of Nova Scotia that is considered a low to medium risk of groundwater having elevated concentrations of uranium, iron, manganese and low pH that may exceed the Guidelines for Canadian Drinking Water Quality.

Water treatment requirements, if any, will depend on the actual quality of water withdrawn from the planned water supply wells and whether the water quality conforms to the Canadian Drinking Water Quality Guidelines. Treatment costs will depend on the type of treatment system employed and the quantity of water withdrawn from the wells on a daily basis.

8.0 Evaluation of Potential Effects

8.1 Potential Well Interference

A calculated estimate of the radius of influence of each water well can be made by using the Theis method that is provided in the Nova Scotia Environment Groundwater Toolkit. The following chart provides a graphical illustration of the expected drawdown from wells withdrawing water at a rate of 1,000 litres per day from the granite aquifer. The results indicate less than 1.0 metre of drawdown at 15 metres radius from each water supply well. If we consider each lot will be 0.5 hectares in size, the risk of interference between adjacent wells is very low.



Whites Lake Property, N.S. Level 1 Groundwater Assessment February 27, 2025

8.2 Potential Effects on Surface Water and the Environment

The proposed development may have an influence on surface water resources by increasing the amount of impervious surfaces within the Property after full build-out. The degree to which the facility will affect surface water resources will depend on the amount of the Property covered by hard surfaces such as roofs, paved areas, concrete areas and lawns, and the mitigating measures that are included in the development.

8.3 Risk of On-Site Septic Systems on Water Wells

The waste water management plan for the Property is to construct onsite, septic systems, one system per lot in accordance with Provincial guidelines.

8.4 NSECC Well Construction Regulations

Planned water wells on the Property should be constructed in conformance with the Nov Scotia Provincial guidelines.

8.5 <u>Mitigation Measures for Low Yield Wells</u>

In the event a property owner constructs a water well that demonstrates a yield on the lower end of the expected yields and determines the well cannot provide a suitable quantity of water to the property, the following methods could be employed:

- 1) Construct the well to a deeper total depth (Cost Estimate = \$2,000 to \$4,000);
- 2) Conduct a hydrofrac of the well. (Cost Estimate = \$4,000)

9.0 Summary

Proposed plans for the 11.6 hectare Property consist of a residential development including 12 individual lots with the potable water supplies consisting of private wells, one well per lot. The following is a summary of the findings of this report.

Summary

Total Size of Property = 11.6 hectares

Number of Lots & Wells = 12

Anticipated Yield of Wells = 10 to 20 litres per minute

Anticipated Total Withdrawals = 8,000 to 10,000 litres per day

Anticipated Per Well Withdrawals = 660 to 830 litres per day per well


Groundwater Recharge = 26,000 litres per day

Risk of Well Interference = very low

The results of this Level 1 Groundwater Assessment indicate the quantity of water required by the proposed residential development has a high probability of being supplied with fresh water from groundwater resources available within the Property.

The quality of groundwater on the Property is currently unknown and will depend on the results of well drilling and water sample analyses.

Appendix A Survey Plan



Certified Wel	10000	Drilled W		Loebaran	fell No.
Name /au/			Well Owne	er/Contractor Infor	
Certificate No.	0 1100	Well drilled for: Owner		ZACI	HARY LAVERS
Company Us/	Tu (Tour 1)	or Contractor/Builder/Cons	ultant/etc.		
Address	- Cigiga	Civic Address of well	740 1	ROSPECT	- RD.
		Lot No. and Subdivision of	well W.F	HITTES L	AKE
Helpers Name(s)		county HACI	CAY	Postal Code	Phone
		Nearest Community in:			
	Stratigra		NO ALIAS CO NO IVIA) BUOK	
Depth in feet From To Colour		of Overburden/Bedrock	Water Wel		Well Location
05 000			Found Ske	Property (PID)
5 /40 mi	a grain	te		GPS (WGS84	UTM) thing m
140/65 Sted	oron	te	M		ting m
			YN	11	
			MM	III NS Alias	NS Map Book
				Page	Collumn Row
				Roam	er Letter Roamer Number
	 		YN	l v	Vell Location Sketch
			YN		SEPTE
) (
			M	;	Taw I I
			Y		
	Attach Another Shaet if Ne	eded			Rosn
Well Consti	ruction Information	Clearance	D' I I II		
alah dan di dan	1/6	- Citarano	Distance to Nea	rest	Water Yield
otal depth below surface	165	ft Oil tank			Water Yield
epth to bedrock	5	ft Oil tank	er boundary 100 f	Method:	Air blown 🔲 Ball (1) Fump
	5	ft Oil tank	er boundary 100 f	method: 0	igpm Curation hrs
Pepth to bedrock	5 ntered 90	ft Oil tank	er boundary 100 f	Method: 0 / Rate / S	igpm Curation hrs
Pepth to bedrock	5 ntered 90	ft Oil tank	er boundary 100 f PROSPECT ge system 60	Method: A Flate Fit Depth to water	igpm Curation hrs ft at end of test ft
valer bearing fractures encour 50 ft Vell Casing uter Casing	ntered 90 It t	ft Oil tank ft Roadway out ft Road name f ft On-site sewa Off-site sewa	er boundary 100 f PRUSPECT ge system 60 ge system 100 f	fit Method: A Flate Fl	igpm Duration hrs ft at end of test ft
Depth to bedrock	5 milered 90 _ftft	ft Oil tank ft Roadway out ft Road name ft On-site sewa Off-site sewa Cesspool or c	er boundary 100 f RDSPECT ge system 60 ge system 400 f other potential	Method: O / Flate / Fl	Lir blown Ball Drump Ligpm Curation hrs ft at end of test ft vered to ft
Depth to bedrock Water bearing fractures encount 50 ft Vell Casing Fuller Casing	ntered 90 It t	ft Oil tank ft Roadway out ft Road name f ft On-site sewa Off-site sewa	er boundary 100 f RDSPECT ge system 60 ge system 400 f other potential	Method: O / Rate / S Fate / S Test depth Test depth to water Total drawdown Water level reco	igpm Curation hrs ft at end of test ft verad to fts hrs mins
repth to bedrock // Ater bearing fractures encount // 50 ft // Coll Casing uter Casing om	Solution	ft Oil tank ft Roadway out ft Road name ft On-site sewa Off-site sewa Cesspool or source of con (please identi	er boundary 100 f RUSPECT ge system 60 ge system 400 f other potential attamination fy source)	Method: 4 fit Flats 5 Test depth 1 fit Dapth to water 1 fit Total drawdown 4 Water level reco	igpm Curation hrs ft at end of test ft verad to fts hrs mins
repth to bedrock /ster bearing fractures encour / 50 ft /ell Casing uter Casing om 0 To 20 fameter 9		ft Oil tank ft Roadway out ft Road name ft On-site sewa Off-site sewa Cesspool course of con (please identi	er boundary 100 f RDSPECT ge system 60 ge system 400 f other potential	Method: Method	igpm Curation hrs ft at end of test ft wered to ft hrs mins
repth to bedrock /ster bearing fractures encour / 50 ft /ell Casing uter Casing om 0 To 20 fameter 9	ft from To Diameter Wall Thickness	ft Oil tank ft Roadway out ft Road name ft On-site sewa Off-site sewa Cesspool or source of con (please identi in in Watercourse	er boundary 100 f RNSPECT ge system 60 ge system 100 f other potential attamination ty source)	Method: A Method	igpm Curation hrs ft at end of test ft wered to ft hrs mins
repth to bedrock //aler bearing fractures encount // to t // t	ft from To Diameter Wall Thickness	ft Oil tank ft Roadway out ft Road name ft On-site sewa Off-site sewa Cesspool or source of con (please identi in in Watercourse	er boundary 100 f RUSPECT ge system 60 ge system 400 f other potential attamination fy source)	Method: A Method	igpm Curation hrs ft at end of test ft wered to ft hrs mins
repth to bedrock // Ater bearing fractures encount / SO ft // Itel Casing uter Casing com O To O iameter / Itel aterial: I steel or STM spec.	ft ft tt ft f	ft Oil tank ft Roadway out ft Road name On-site sewa Off-site sewa Cesspool or Source of con (please identi in Watercourse Colour Final Si	er boundary 1004 PRUSPECT ge system 1004 other potential stamination fy source) ft Well Taste Taste	Method: fit Flats S Test depth fit Dapth to water: total drawdown Water level reco atvarrate lest ended Depth to static is in Overflow Water Quality Odour Water Use	Lir blown Ball Drump Ligpm Curation hrs ft at end of test ft Lyerad to
repth to bedrock / So ft / Coll Casing uter Casing om O To O immeter all Thickness steel or STM spec. nogth of casing above ground	ft ft tt ft f	ft Oil tank ft Roadway out ft Road name ft On-site sewa Off-site sewa Cesspool or cource of con (please identi in Watercourse Colour Final St	er boundary 100 f PROSPECT ge system 100 f other potential Itamination fy source) ft Well Taste Itatus of Well	Method:	Lir blown Ball Drump Ligpm Curation hrs ft at end of test ft Livered to ft Livered ft Livered ft Livered ft Livered ft
repth to bedrock / Start bearing fractures encour / Start bearing fractures encour / Start bearing fractures encour / Start Casing / Star	fit	ft Oil tank ft Roadway out ft Road name ft On-site sewa Off-site sewa Cesspool or concept of concept of concept of concept on the concept of concept of concept on the concept of concept on the concept of concept of concept on the concept of concept on the concept of concept of concept on the concept of concept on the concept of concept of concept on the concept on the concept of concept on the concept of concept on the concept on the concept on the concept of concept on the concept on the concept of concept on the concept of concept on the concep	er boundary 100 f PROSPECT ge system 100 f other potential Itamination fy source) ft Well Taste Itatus of Well	Method:	Lir blown Ball Drump Ligpm Curation hrs ft at end of test ft Livered to
repth to bedrock // fater bearing fractures encount // 50 ft // fill Casing uter Casing To 20 iameter fall Thickness / 9X atterial: steel or STM spec. ingth of casing above ground driveshoe: type grout: type Bur	fit	ft Oil tank ft Roadway out ft Road name of On-site sewa Off-site sewa Cesspool or of Source of con (please identi in in Watercourse Colour Final Si Water sup Observatio Test Hole	er boundary 100 f PROSPECT ge system 100 f other potential Itamination fy source) ft Well Taste Latus of Well poly on Well	Method:	Direction Ball Drump Ligpm Duration hrs ft at end of test ft Light hrs mins Light
repth to bedrock // fall bearing fractures encount // 50 ft // fall Casing uter Casing om	ft ft tt ft f	ft Oil tank ft Roadway out ft Road name of On-site sewa Off-site sewa Cesspool or of Source of con (please identi in in Watercourse Colour Final Si Water sup Observatio Test Hole Recharge	er boundary 100 f PROSPECT ge system 100 f other potential alamination fy source) ft Well Taste Latus of Well Well Well	Method:	Direction Ball Drump Ligpm Duration hrs ft at end of test ft wered to ft hrs mins evel Other Method of Drilling Rotary Cable Tool
repth to bedrock / Start bearing fractures encour / Start bearing fractures encour / Start bearing fractures encour / Start Casing / Start Casing / Start Casing above ground / Start Spec. / Sta	fit	ft Oil tank ft Roadway out ft Road name ft On-site sewa Off-site sewa Cesspool or of source of con (please identi in in Watercourse Colour Final Si Water sup Observati Test Hole Recharge Abandoned	er boundary 100 f PROSPECT ge system 100 f other potential Itamination fy source) ft Well Taste Latus of Well by by Well by insufficient supply	Method:	Direction Ball Drump Ligpm Curation hrs ft at end of test ft wered to ft hrs mins evel ft Other Method of Drilling Rotary Cable Tool Jet
repth to bedrock / So ft / S	fit	ft Oil tank ft Roadway out ft Road name ft On-site sewa Off-site sewa Cesspool or source of con (please identi in in Colour Final Si Water sup Observati Test Hole Recharge Abandoner	ge system 4004 ge system 4004 other potential lamination fry source) ft Well Taste Latus of Well by insufficient supply d, poor quality	Method:	Direction Ball Drump Ligpm Curation hrs ft at end of test ft Light Hrs Light
Vell Casing Valer bearing fractures encour 50	ft f	ft Oil tank ft Roadway out ft Road name on-site sewa Off-site sewa Cesspool or source of con (please identi in in Colour Final Si Water sup Observati Test Hole Recharge Abandoned Abandoned Abandoned Abandoned	er boundary 100 f PROSPECT ge system 100 f other potential Itamination fy source) ft Well Taste Latus of Well by insufficient supply d, poor quality d, salt water	Method:	igpm Duration hrs ft of end of test ft vered to ft Nother Other Rotary Cable Tool Jet Other Drilling Fields Drilling Fields
vater bearing fractures encour / SO ft Vell Casing uter Casing rom O To O O iameter Stall Thickness / SX aterial: Steel or stall of casing above ground of driveshoe: type	ft f	ft Oil tank ft Roadway out ft Road name ft On-site sewa Off-site sewa Cesspool or source of con (please identi in in Colour Final Si Water sup Observati Test Hole Recharge Abandoner Abandoner Unfinished	er boundary 100 f PROSPECT ge system 100 f other potential Itamination fy source) ft Well Taste Latus of Well by insufficient supply d, poor quality d, salt water	Method:	Direction Ball Drump Ligpm Curation hrs ft at end of test ft Light Hrs Light
vater bearing fractures encour / SO ft Vell Casing uter Casing To 20 iameter fall Thickness / SX aterial: steel or STM spec. ingth of casing above ground driveshoe: type grout: type ### But grout: type ### But grout: type ### But ### Git from gth ft from gth ft from ### If from ###	ft f	ft Oil tank ft Roadway out ft Road name on-site sewa Off-site sewa Cesspool or cource of con (please identi in watercourse Colour Final Si Test Hole Recharge Abandonet Abandonet Unfinished	er boundary 100 f R SPECT ge system 60 ge system 60 ge system 60 ft Well Taste Taste Latus of Well Well d, insufficient supply d, poor quality d, salt water	Method:	igpm Duration hrs ft of end of test ft vered to ft Nother Other Rotary Cable Tool Jet Other Drilling Fields Drilling Fields
repth to bedrock Vater bearing fractures encour Vell Casing Vell Ca	fit	ft Oil tank ft Roadway out ft Road name on-site sewa Off-site sewa Cesspool or cource of con (please identi in watercourse Colour Final Si Test Hole Recharge Abandonet Abandonet Unfinished	er boundary 100 f PROSPECT ge system 100 f other potential Itamination fy source) ft Well Taste Latus of Well by insufficient supply d, poor quality d, salt water	Method:	igpm Duration hrs ft of end of test ft vered to ft Nother Other Rotary Cable Tool Jet Other Drilling Fields Drilling Fields
repth to bedrock / So ft / S	ft f	ft Oil tank ft Roadway out ft Road name On-site sewa Off-site sewa Cesspool or Source of con (please ident) in in Colour Final Si Watercourse Cobservatic Test Hole Recharge Abandoned Abandoned Unfinished Other ft	ge system 60 ther potential stamination fly source) ft Well Taste 8 tatus of Well by by by Well Well d, insufficient supply d, poor quality d, salt water Certification	Method:	Dirilling Fleids Type: Mail to: Nova Scotla Department of
repth to bedrock / So ft / S	fit	ft Oil tank ft Roadway out ft Road name On-site sewa Off-site sewa Cesspool or Source of con (please ident) in in Colour Final Si Watercourse Cobservatic Test Hole Recharge Abandoned Abandoned Unfinished Other ft	ge system 60 ther potential stamination fly source) ft Well Taste 8 tatus of Well by by by Well Well d, insufficient supply d, poor quality d, salt water Certification	Method:	Dirilling Fleids Type: Mail to: Nova Scotia Department of Environment 30 Damascus Road, Suite 115
repth to bedrock Vater bearing fractures encour Vell Casing Vell Ca	fit	ft Oil tank ft Roadway out ft Road name ft On-site sewa Off-site sewa Cesspool or source of con (please identi in in Colour Final Si Water sup Observati Test Hole Recharge Abandoner Abandoner Unfinished Other ft I certify this w the Nova Scoti	ge system 60 ge sy	Method:	In blown Ball Drump In igpm Duration hrs If the price of test ft the street of the s
repth to bedrock / So ft / S	fit	ft Oil tank ft Roadway out ft Road name ft On-site sewa Off-site sewa Cesspool or cource of con (please identi in in Colour Final Si Water sup Observati Test Hole Recharge Abandone Abandone Unfinished Other ft I certify this withe Nova Scott Regulations.	ge system 60 ge sy	Method:	Dirilling Fleids Type: Mail to: Nova Scotia Department of Environment 30 Damascus Road, Suite 115

Whites Lake Property, N.S. Level 1 Groundwater Assessment February 27, 2025