

NOTE: THIS MAP IS A GRAPHIC REPRESENTATION OF SURVEY DATA, ENTERED BELOW. SUCH DATA DESCRIBES THE VIEW PLANES. THE EFFECT OF THIS BY-LAW ON ANY PROPERTY MUST BE SPECIFICALLY ASCERTAINED.

TABLE A VIEWING POSITIONS

VIEWING POSITION	NORTH COORDINATE	EAST COORDINATE	ELEVATION
A	4,945,697.066m	25,573,074.966m	62.980m
B	4,945,637.751m	25,573,076.973m	72.551m
C	4,945,523.329m	25,573,117.316m	65.327m
D	4,945,505.597m	25,573,012.488m	67.369m

TABLE B VIEW PLANES

VIEW PLANES	BOUNDARY BEARING	BOUNDARY BEARING	ZENITH ANGLE
1	N24° 36' 50"W	N12° 41' 50"W	91° 58' 30"
2	N28° 03' 50"E	N36° 56' 20"E	92° 47' 30"
3	N51° 05' 00"E	N59° 49' 30"E	92° 57' 40"
4	N52° 58' 40"E	N68° 07' 00"E	92° 56' 30"
5	N74° 42' 00"E	S86° 36' 30"E	92° 53' 40"
6	S73° 32' 10"E	S63° 20' 30"E	93° 51' 00"
7	S63° 25' 30"E	S59° 23' 20"E	91° 26' 40"
8	S59° 23' 20"E	S34° 39' 50"E	91° 25' 20"
9	S38° 11' 20"E	S22° 40' 50"E	90° 46' 50"
10	S28° 55' 40"E	S16° 09' 50"E	90° 42' 00"


NOTES: BOUNDARY BEARING IS THE BEARING OF EACH BOUNDARY OF ALL VIEW PLANES SHOWN ON THIS MAP.

THE ZENITH ANGLE IS THE ANGULAR MEASUREMENT FROM THE VERTICAL AXIS TO THE VIEW PLANE.

ELEVATIONS ARE REFERENCED TO CANADIAN GEODETIC VERTICAL DATUM 2013 (CGVD2013).

COORDINATES REFER TO ZONE 5, CENTRAL MERIDIAN 64°30' WEST, OF THE NOVA SCOTIA 3° MTM PROJECTION, NAD83 CSRS (2010) DATUM.

ALL POINTS, E, F, G, H, I, J, K, L, M, N, O, P, Q, R, S, T, U, V, W, X HAVE AN ELEVATION OF 0.00m



"VIEW MAP"



HALIFAX

Regional Centre
Secondary Municipal Planning Strategy

Map 6

Halifax Citadel View Planes
(detailed View Plane Geometry)

SCALE
1 : 20,000

DATE
11/30/2019